

SECTION 01310 - CONSTRUCTION PROGRESS SCHEDULES

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Format.
- B. Content.
- C. Revisions to schedules.
- D. Submittals.

1.02 RELATED SECTIONS

- A. Section 01011 - Summary of Work.
- B. Section 01027 - Applications for Payment: Application for payment.
- C. Section 01300 - Submittals: Shop drawings.

1.03 REFERENCES

- A. AGC (Associated General Contractors of America) publication "The Use of CPM in Construction - A Manual for General Contractors and the Construction Industry".

1.04 FORMAT

- A. Prepare schedules starting with Notice to Proceed date through substantial completion, as a horizontal bar chart or Gantt chart with separate bar for each major portion of Work or operation, identifying first work day of each week.
- B. Sequence of Listings: The chronological order of the start of each item of Work.
- C. Scale and Spacing: To provide space for notations and revisions.
- D. Sheet Size: Maximum 30" x 42" OR multiples of 8½" x 11".

1.05 CONTENT

- A. Show complete sequence of construction by activity, with dates for beginning and completion of each element of construction.
- B. Identify each item by specification section number.
- C. Identify work of separate stages and other logically grouped activities.
- D. Provide sub-schedules for each stage of Work.
- E. Provide sub-schedules to define critical portions of the entire schedule.
- F. Include conferences and progress meetings in schedule.
- G. Show accumulated percentage of completion of each item, and total percentage of Work completed, to coincide with schedule of values in each application for payment.

- H. Provide separate schedule of submittal dates for shop drawings, product data, and samples, including Owner furnished products and dates reviewed submittals will be required from Architect/Engineer. Indicate decision dates for selection of finishes.
- I. Include scheduling for fabrication of structural steel.
- J. Include scheduling of erection sequence of building structural steel, precast walls and delivery to site.
- K. Include scheduling of erection sequence of building precast walls and delivery to site.

1.06 REVISIONS TO SCHEDULES

- A. Indicate progress of each activity to date of submittal, and projected completion date of each activity.
- B. Identify activities modified since previous submittal, major changes in scope, and other identifiable changes.
- C. Provide narrative report to define problem areas, anticipated delays, and impact on Schedule. Report corrective action taken, or proposed, and its effect including the effect of changes on schedules of separate contractors.

1.07 SUBMITTALS

- A. Submit initial schedules within 15 days after date of Owner-Contractor Agreement. After review, resubmit required revised data within seven days.
- B. Submit revised Progress Schedules with each Application for Payment.
- C. Submit the number of opaque reproductions which Contractor requires, plus two copies which will be retained by Architect/Engineer.

1.08 DISTRIBUTION

- A. Distribute copies of reviewed schedules to Project site file, Subcontractors, suppliers, and other concerned parties.
- B. Instruct recipients to promptly report, in writing, problems anticipated by projections indicated in schedules.

PART 2 - PRODUCTS

Not Used.

PART 3 - EXECUTION

Not Used.

END OF SECTION