

**ADDENDUM NO. 4  
ROWAN COUNTY EMS FACILITY  
MOREHEAD, ROWAN CO., KENTUCKY**

**Bid Date: May 18, 2020**

**Issue Date: May 14, 2020**

**Item No. 1:**

**Sheet E-1**

1. Change panel A from 3 phase, 4 wire to single phase, 3 wire.
2. Change wire feed from “4 #3AWG copper + #4 ground in 1-1/4” conduit” to “3 #1AWG copper + #6 in 1-1/2” conduit”.
3. Sheet note 8 is not changed.
4. Change sheet note 10 to read: Install two carbon monoxide detectors wired in tandem. Provide carbon monoxide detectors with output signal capable of starting EF-2 when co level is reached. Output signal can be line voltage or low voltage with relay. Provide regular single pole 120V switch to control fan normally. Wire normally open relay (or line voltage output) in parallel with switch which closes when triggered by CO sensor to automatically. CO sensor shall be equipped or wired in a manner such that manual reset is necessary to turn the fan of—fan cannot automatically turn off.
5. Smoke alarm shall provide local alarm only and shall be hard wired from circuit A-1 And shall be tied together.

**Item No. 2:**

**Sheet P-1**

1. PEX piping is acceptable for hot and cold-water piping.
2. Provide 1/2" Armaflex insulation on all hot and cold-water domestic water piping.

End of Addendum No. 4